

Project Completion Timeline



Rendering of Meta's planned data center campus near Nashua in Kansas City's Northland, with the on-site high-voltage substation visible at left. The project broke ground in 2022, and Meta initially announced the nearly 1 million–square-foot facility would be operational by 2024 1. However, local reports indicate construction and permitting delays have pushed back the timeline. As of early 2025, the first "H"-shaped data center building was still being completed, delaying full operations (and related tax revenue) until around late 2024 or 2025 2. In short, the data center's opening has slipped past the original 2024 target, with updated expectations pointing to a 2025 timeframe for initial operation.

Electrical Load (MW Demand)

The Meta data center will impose a massive electrical load on the grid. The Golden Plains Technology Park campus (where Meta's site is located) is planned to support up to **750 MW** of IT load at full build-out ³ ⁴. Meta's first phase is a large portion of this campus, and its power needs are on the order of several *hundred* megawatts. Evergy – the regional utility – has indicated that new hyperscale customers like Meta (along with a new Google data center and a Panasonic plant) account for roughly **800 MW** of added demand in the Kansas City area ⁵. To put the scale in perspective, the combined energy demand of the Meta and Google campuses is equivalent to about *100 Walmart stores or 40 hospitals* ⁶. This unprecedented load is driving significant expansion of generation and transmission infrastructure, including plans for new power plants and ~3,000 MW of additional renewable energy to support the data centers' needs ⁶ ⁷.

Grid Interconnection Voltage

Meta's Nashua-area data center will connect at **high-voltage transmission level** to handle its enormous power draw. The campus sits adjacent to Evergy's **Nashua** substation, through which it ties into the *345 kV* "Iatan–Nashua" bulk power line on the SPP grid ⁸ . In fact, the development of the data center included

adding a new 345 kV/161 kV transformer at the Nashua substation to step down power for the facility ⁸. By interconnecting at 345 kV, the data center can be served without overloading lower-voltage distribution lines, and it gains direct access to wholesale power (including the 100% renewable energy Meta has contracted for this site ⁹). In summary, the project is being fed from the **345 kV** transmission grid, ensuring sufficient capacity and reliability for Meta's large-scale energy needs.

Sources: Kansas City Business Journal; Smart Energy Decisions; Missouri Partnership; Commercial Property Executive; DataCenterDynamics; Show Me Institute; Reuters; Diode Ventures; Missouri PSC filings; Evergy/ SPP planning documents.

- 1 Meta Selects Missouri For New Sustainable Data Center | Smart Energy Decisions https://www.smartenergydecisions.com/news/meta-selects-missouri-for-new-sustainable-data-center/
- ² ⁶ ⁷ Kansas City's Data Center Boom: Another Costly Gamble Show Me Institute https://showmeinstitute.org/blog/subsidies/kansas-citys-data-center-boom-another-costly-gamble/
- ⁹ Meta Announces \$800M Data Center in Kansas City Commercial Property Executive https://www.commercialsearch.com/news/meta-announces-800m-data-center-in-kansas-city/
- 4 Diode Ventures

https://www.diodeventures.com/insights/how-kansas-city-is-cracking-the-code-on-data-centers

- 5 Evergy's pipeline of power users like data centers jumps to 11.2 GW | Reuters https://www.reuters.com/business/energy/utility-evergy-misses-fourth-quarter-profit-estimates-higher-costs-2025-02-27/
- 8 Microsoft Word First Amended Application to Transfer Assets 7-3-2012.DOC https://www.efis.psc.mo.gov/Document/Display/111029